LIFESAVING SYSTEMS CORPORATION

LSC Test Report Number: F-730-452
Revision: A

Load Testing of #452



PROPRIETARY & CONFINDENTIAL

THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION OWNED BY LIFESAVING SYSTEMS AND MAY NOT BE DUPLICATED, COMMUNICATED TO OTHER PARTIES OR USED FOR ANY PURPOSE WITHOUT THE EXPRESS WRITTEN PERMISSION OF LIFESAVING SYSTEMS CORP.

Prepared by: _____ Date: 10-SEP-2019
Thomas Beach, Engineering

Approved by: Robert Jerger Date: 11/19/2019
Robert Jerger, Quality

Document History				
Revision	**Issue Date**	**Description of Revision/Modification**	**Revised by**	**Approved by**
A	10-SEP-2019	Initial Release	-	

Table of Contents

PURPOSE: 4
ACRONYMS AND ABBREVIATIONS: 4
TEST FACILITY: 4
REFERENCE: 4
SUMMARY OF TESTS PERFORMED & RESULTS: 5
SECTION 1- TEST CONDITIONS & EQUIPMENT: 6
1.1 ENVIRONMENTAL CONDITIONS 6
1.2 TOLERANCES 6
1.3 INSTRUMENTS AND EQUIPMENT 6
1.4 CALIBRATION 6
SECTION 2- LOAD TEST: 7
2.1 SCOPE 7
2.2 APPRATUS 7
2.3 PROCEDURE 7
2.4 ANALYSIS OF RESULTS 8
2.5 PHOTOGRAPHS 9

PURPOSE:

The purpose of this report is to show the load strength of the slide bar adjuster, part number 452. Successful completion shall confirm the adjustment hardware satisfies the requirement of withstanding a load of 5kN without permanent distortion listed in the standard AS/NZS 1891.1:1995, clause 3.3.3.

ACRONYMS AND ABBREVIATIONS:

LSC – Lifesaving Systems Corp.
N/A – Not Applicable
P/N – Part Number
S/N – Serial Number
Lbf – Pound-Force
N – Newton

TEST FACILITY:

Testing and inspection was performed at Lifesaving Systems Corporation's (LSC) manufacturing facility located in Apollo Beach, Florida by LSC personnel.

REFERENCE:

AS/NZS 1891.1:1995

Australian/New Zealand Standard

Industrial fall-arrest systems and Devices

Part 1: Safety belts and harnesses

SUMMARY OF TESTS PERFORMED & RESULTS:

Section	Test Description	Results
2.4	Load Test	The adjusting hardware can withstand a minimum load of 1,124lbf (5kN) without permanent distortion.

SECTION 1- TEST CONDITIONS & EQUIPMENT:

1.1 ENVIRONMENTAL CONDITIONS

Load test shall be performed at a temperature of 75 ± 5°F, and a relative humidity of 50 ±15%. The temperature and humidity shall be recorded at time of test.

1.2 TOLERANCES

The load cell tolerances shall be maintained within all applicable specified tolerances.

- 2000lbf ± 2lbf
- 4000lbf ± 3lbf
- 6000lbf ± 4lbf

1.3 INSTRUMENTS AND EQUIPMENT

LSC Tool No.	Test Equipment	Description	Cal. Date	Cal. Due
88	Cell, Load	Force Measurement: 10,000lb	6/4/2019	6/4/2020
57	RH/Temp Monitor	Temp and Humidity Monitor	6/3/2019	6/4/2020
85	Calipers	Dimensional Measurement:	1/2/2019	1/2/2020

1.4 CALIBRATION

The instruments and equipment are calibrated according to manufacturer's specifications and calibration is traceable to the National Institute of Standards and Technology (NIST). Calibration records are maintained on file at Lifesaving Systems Corp. Photograph of the load cell calibration sticker can be found in Section 2.5 of this report.

SECTION 2- LOAD TEST:

2.1 SCOPE

The load test is performed to determine the strength of the slide bar adjuster.

2.2 APPRATUS

- Hydraulic pull tester
- Load Cell
- Type-13 Mil-Spec Nylon Webbing

2.3 PROCEDURE

Step 1. Measure the overall height of the slide bar adjuster and record results.

Step 2. Mount the slide bar adjuster with webbing straps inside the hydraulic pull tester by looping one strap through the top grip.

Step 3. Mount the other end of the webbing strap to the bottom grip. The slide bar adjuster shall be in a vertical orientation before load testing.

Step 4. Increase the force at a rate of 500N (112lbf) every 3 seconds until the target load of 5kN (1,124lbf) is achieved or ultimate failure occurs.

Step 5. Release the force and measure the height of the slide bar adjuster for material deformation. Record results.

2.4 ANALYSIS OF RESULTS

Table1.

Target Load (lbf)	Adjuster Measurement Pre-Test (in)	Load Cell Reading (lbf)	Adjuster Measurement Post-Test (in)	Comment
0	0	0	0	-
1,124	1.71	1,292	1.71	No Distortion, No Webbing Slippage

Temperature and Relative Humidity Reading: 77.2°F, 53%

2.5 PHOTOGRAPHS



Test Setup



Load Cell: Calibration Sticker



Load at 1,292lbf



Post Measurement